


CITY OF PULLMAN - PUBLIC WORKS

N. GRAND WATERLINE REPLACEMENT PROJECT



DESCRIPTION

This project will replace old cast iron water main along N. Grand Avenue with approximately 2,300 lineal feet of new 6- to 12-inch PVC pipe. To facilitate waterline installation, the work also includes removing and replacing pavement (both Portland Cement Concrete and Hot Mix Asphalt), curb and gutter, and concrete sidewalk. Fire hydrants will be installed at three new locations as a result of the project. The project will take roughly 3 months to complete with the work generally progressing from south to north.

LOCATION

Improvements along N. Grand Avenue will occur from the Mobil gas station northward to just past Golden Teriyaki. Construction will also require work at the intersections of Nye Street and Stadium Way. A majority of the work is proposed on the west side of N. Grand Avenue, although periodic improvements are required on the east side to allow for necessary fire hydrant installations, waterline tie-ins, and water service connections.

PUBLIC IMPACTS

Construction of this project is expected to primarily impact vehicular travel and access to businesses located within or near the project limits. N. Grand Avenue will be reduced to two lanes of traffic (one lane in each direction) for a majority of the work. Temporary traffic control devices will be set-up in varying stages and locations to minimize traffic impacts and lane closures to the extent practicable. Typical construction hours are 7:30 am to 4:30 pm on weekdays, with lane closures and traffic control measures expected around the clock. Travel delays should be expected and drivers are asked to proceed through the project area slowly while remaining attentive to potential variations. Use of one-lane traffic (with flaggers) will only be used if necessary to ensure the safety of the workers and the public during the required construction activities. Temporary closure of the Nye Street/N. Grand Avenue intersection is needed for a portion of the work. At least one access driveway to each business fronting N. Grand Avenue will be maintained during the project.

Additional impacts include periodic, short-term disruptions to water service to allow for the necessary waterline connections and tie-ins. The City will contact affected businesses and residences as the project proceeds and more specific information on dates and times is known.

PROPOSED SCHEDULE

Start: Monday May 8th, 2017
Estimated End: Friday August 11th, 2017

QUESTIONS

Contact the Public Works Department at:
(509) 338-3213

