

CITY OF PULLMAN - PUBLIC WORKS

BISHOP BLVD BRIDGES DECK RESURFACING PROJECT



DESCRIPTION

This project will resurface two bridge decks on Bishop Blvd (one at Paradise Creek, the other at the South Fork Palouse River), including full-depth removal of hot mix asphalt on the existing bridge decks, bridge deck repair, and then placing a new waterproof membrane and a 3-inch hot mix asphalt overlay. The work also includes resurfacing of bridge approaches with a 2- to 3-inch partial-depth hot mix asphalt removal and subsequent overlay and construction of five (5) new curb ramps. The project will take approximately six (6) weeks to complete with the work progressing concurrently at both bridge locations.

LOCATION

Infrastructure improvements at the Paradise Creek bridge location will extend from just south of the Quality Inn driveway entrance to Bleasner Drive. Improvements at the South Fork Palouse River bridge location will commence from Johnson Avenue and continue to just south of the northern driveway entrance to The Professional Mall, including the intersection of Bishop Blvd and Professional Mall Blvd. Temporary traffic control measures and alterations are anticipated leading up to and between both bridge locations.

PUBLIC IMPACTS

Construction of this project is expected to primarily impact vehicular travel and access to businesses located within or near the project limits. Bishop Blvd will be reduced to two lanes of traffic (one lane in each direction without a designated turn-lane) for a majority of the work. Temporary traffic control devices will be set-up in varying stages and arrangements to minimize traffic impacts to the extent practicable while accommodating construction throughout the full roadway width. Typical construction hours are 7:00 am to 4:00 pm on weekdays, with lane closures and traffic control measures expected around the clock. Travel delays are likely and drivers are asked to proceed through the project area slowly while remaining attentive to frequent traffic control variations.

Temporary closure of the roadway at each bridge location is necessary for paving operations, tentatively scheduled for mid to late July and limited to a 72-hour maximum combined time-frame. Detours will be in-place during such closures and at least one driveway access will be maintained to businesses fronting Bishop Blvd. The City will provide additional details to the public on these closures as the project proceeds and further information is known.

PROPOSED SCHEDULE

**Start: Monday
June 25th, 2018**
**Estimated End: Friday
August 3rd, 2018**

QUESTIONS

**Contact the Public
Works Department at:
(509) 338-3213**

